



NOTE:

1. IF THE INSULATION COMPRESSIVE STRENGTH IS INSUFFICIENT FOR THE EQUIPMENT WEIGHT, INSTALL WOOD UNDER THE EQUIPMENT CARRYING SLEEPER, MATCHING THE HEIGHT OF THE INSULATION.



ROOF PENETRATION SERIES

EXPOSED WOOD EQUIPMENT SUPPORT SLEEPER

DRAWING #

511

SCALE

N.T.S.

SYSTEM

MA/FA/BA

ISSUE/ REVISION DATE

9-01-09