

- 1. FOR STEEL ROOF DECKS: FILL TOPSIDE OF STEEL DECK FLUTES WITH CLOSED CELL SPRAY FOAM INSULATION PRIOR TO THE INSTALLATION OF ABOVE DECK INSULATION A MINIMUM OF 12" [305 mm] FROM FACE OF WALL ON EACH SIDE, BOTH SIDES OF WALL.
- AIR SEAL WALL-TO-UNDERSIDE OF ROOF DECK INTERFACE AS PER ARCHITECTURAL DRAWINGS.

Cold to Warm Transition - IMP Below Deck



We protect what matters most™

Legend: Heat Weld **\$\$\$\$\$\$\$\$**

Adhesive

Product:

EverGuard TPO

Installation: Cold Storage Systems

Maximum Warranty:

Date:

2/13/2025

Scale:

Not To Scale

Detail No. 075423